



**GUIDELINES FOR INITIATION AND COMPLETION OF SNOW  
REMOVAL**

<b>ROAD CATEGORY</b>	<b>NET SNOW ACCUMULATION FOR REMOVAL START</b>	<b>TYPE OF OPERATION</b>	<b>TIME TO COMPLETE REMOVAL</b>
<b>EXPRESSWAYS</b>	20 to 30 cm	Full operation (Overtime if required)	3 Days
<b>RED</b> <b>[Selected sections]</b> *Without or small <b>Boulevard</b>  *Commercial <b>on-street Parking</b>	20 to 30 cm  30+ cm	Partial Operation (8 hr shifts)  Full Operation (Overtime if required)	2 Weeks
<b>BLUE</b> <b>Bus Routes</b> <b>Collector Roads</b> <b>Local Streets</b> <b>with hills</b>	20 to 30 cm  30+ cm	Partial Operation (8 hr shifts)  Full Operation (Overtime if required)	2 Weeks
<b>GREEN</b> <b>Local Streets</b>	-	(Only required for sight lines, etc.)	-
<b>YELLOW</b> <b>Local Streets</b> <b>without</b> <b>Boulevards and</b> <b>with long term</b> <b>on-street parking</b>	30+ cm	Full Operation (Overtime if required)	2 Weeks
<b>DEAD ENDS (or cul-de-sacs)</b> <b>-with limited or no storage space</b> <b>for snow</b>	20 to 30 cm	Full Operation (Overtime if required)	1 Week
<b>LANEWAYS</b>	30+ cm	Full Operation (Overtime if required)	3 Weeks